
Kirk Michael Methodist Church



Gt: 8,8,8,4,4,- Sw: 8,8,8,8,4,8,-,- Ped: 16,8.

This instrument was built by Morgan, or, more probably, Morgan and Pollard, in the late nineteenth century, for the Ebenezer Methodist Church.

The mechanism is mechanical for the manuals, and pneumatic for the pedals and display pipes, and the pitchpine case is of simple, but striking, design and placed in a commanding position. (The 2 semi-circular 'fans' above the console are a unique, if eccentric, touch.)

Aside from Trinity Methodist Church in Douglas, this is the only organ on the Island to have a wooden flute (the Travers Flute on the Great) of triangular, rather than rectangular, cross-section. The builders managed to fit a full-length Diapason bass

into the small swell-box by making the scale of its wooden pipes very small indeed.

The instrument was cleaned and overhauled by Peter Jones in 1990.



